Masson Avenue: 1

Easton Avenue: 3

Angus Avenue: 9

Easton Avenue: 2

Green Avenue: 4

Green Avenue: 5

Sylvan Avenue: 8

Hensley Avenue: 7

Hensley Avenue: 6

TABLE 1: CORING DATA		
CORING LOCATION	AC THICKNESS (INCHES)	AB THICKNESS (INCHES)
B–1	2	4
B–2	2.2	6.5
B–3	3	4
B–4	3	4
B–5	3	5
B–6	3	4
B–7	3	4
B–8	3	4
B–9	3	6
B–10	3	7
B–11	2	7
B–12	2	6

LEGEND:

PAVEMENT TREATMENT AS SHOWN. RESTORE STRIPING AND PAVEMENT MARKINGS PER EXISTING CONDITION.

DIGOUT AREA

CORING LOCATION. SEE TABLE 1: CORING DATA.

CONSTRUCTION NOTES

1 RESTORE STOP BAR AND LEGEND
2 RESTORE CROSSWALK STRIPING
3 RESTORE "KEEP CLEAR" STRIPING AND LEGEND
4 RESTORE STOP LEGEND
5 RESTORE ARROW PAVEMENT MARKING
6 ADJUST TO GRADE EX VALVE AND MANHOLE (<18" ø)
7 ADJUST TO GRADE EX VALVE AND MANHOLE (≥18" ø)
8 REPLACE EX DETECTOR LOOPS

Part 1: Streets #1,2,3

Part 2: Streets #4,5,6

Part 3: Streets #7,8,9

50 25 0 50 100 150
SCALE IN FEET

100% SUBMITTAL
JULY 2021

Call Two Working Days Before You Dig!
1-800-227-2600

Avenues 3-1 Sewer & Water Main Replacement Project

NO.	DESCRIPTION	BY	DATE

City of San Bruno
Public Works Department
567 El Camino Real
San Bruno, CA 94066
Tel: (650) 616-7065, Fax: (650) 794-1443
www.sanbruno.ca.gov

Bellecci & Associates, inc.
Civil Engineering • Land Surveying
4977 Kott Center Pkwy, Suite 210 Pleasanton, CA 94566
(925) 461-4055
www.bellecci.com

PREPARED UNDER THE DIRECTION OF: ANOOP REDDY ADMAL P.E. DATE:

REGISTERED PROFESSIONAL ENGINEER ANOOP REDDY ADMAL No. 76008 CIVIL STATE OF CALIFORNIA

STRIPING & PAVEMENT PLAN

Date: July 2021
Scale: 1" = 50'
Design By: AA
Drawn By: SC
Checked By: DCL
Sheet Number
C9.0
21 of 42 Sheets
City Project No.
11009 & 31012